Bruhath Bangalore Mahanagara Palike

Office of the Executive Engineer
Bruhath Bengaluru Mahanagara Palike
Dasarahalli Zone

"DTS for Kind Approval"

Name of the Work:- Annual Maintenance of Street Lights Package D-4 ward No 14 ~~Bagalagunte~~ in Bagalagunte

Sl. No.	Approved Qty	Description	Unit	Approved Rates	
				in Figures	in words
1	582	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. **36/40 W fluorescent tube light street lighting system.**	Each	685.45	Rupees Six Hundred Eighty Five and Forty Five Paise only
2	104	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. **125W HPMV Park lighting system.**	Each	756.29	Rupees Seven Hundred Fifty Six and Twenty Nine Paise Only
3	2642	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed belowPoles with **250W HPSV street lighting system.**	Each	1019.41	Rupees One thousand Ninteen and forty one paise Only
4	128	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below **400 watts HPSV street light /High mast lighting system.**	Each	1118.08	Rupees One thousand One Hundred and Eighteen eight paise Only
5	168	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for **24 Watt to 40 Watt LED Park/ street lighting system.**	Each	880.01	Rupees Eight Hundred and Eighty and One Paise Only

No. of corrections - Nil - No.

Superintending Engineer (Electrical)
Bruhath Bengaluru Mahanagara Palike

Executive Engineer (Elec)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner

6	265	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for **40 Watt to 65 W LED street Light lighting system.**	Each	1147.43	Rupees Eight Hun and Eighty and One Only
7	121	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for **90W LED street light lighting system.**	Each	1377.66	Rupees One Thousand Three Hundred Seventy seven and Sixty Six Only
8	1	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for**110/120 watt LED street light lighting system**	Each	1575.5	Rupees One Thousand Five hundred Seventy Five and Five paise Only
9	1	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for **150/180 watt LED street light /High mast lighting system.**	Each	1871.51	Rupees One Thousand Eight Hudred Seventy One and Fifty One Paise Only
10	10	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.**300mmx450mmx214mm**	Each	5127.00	Rupees Five Thousand One Hundred Twenty Seven Only
11	22	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947 **100 to 125Amps**	Each	7200.00	Rupees Seven Thousand Two Hundred Only
12	23	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, Indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.**50-63 Amps SP**	Each	723.00	Rupees Seven Hundred and Twenty Three Only
13	24	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	4030.00	Rupees Four Thousand and Thirty Only

No. of corrections - nil -

Superintending Engineer (Electrical)
Bruhath Bengaluru Mahanagara Palike

Executive Engineer (Elec)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner

10	Wiring for lighting/power circuit using one of FRLS PVC Insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.6 **sqmm**	Mtr	70.00	Rupees Seventy Only
100	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.6 **sqmm**	Each	7.00	Rupees Seven Only

No. of corrections - nil -

Executive Engineer(Ele)
BBMP, Dasarahalli Zone

ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡಿದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ:.....(ಶೂನ್ಯ).....

ಆದೀಕಕ ಅಭಿಯಂತರರು (ವಿದ್ಯುತ್)

Scanned by CamScanner